

CORRIGENDUM-1 TO TENDER NO CGI8419P19

The quantity, Unit and internal rate of SOQ from item No 11 to 17 of the TENDER NO CGI8419P19 has been interchanged due to inadvertent typographical error. Bidders are requested to read the same correctly and consider the quantity under the rate column, rate under Unit Column and Unit under Quantity column. All other terms and conditions and total value of the tender will remain same. The correct SOQ from item 11 to 17 will be as per below mentioned table.

SL. NO.	DESCRIPTION OF WORK	QTY (A)	UNIT	OIL'S RATE PER UNIT (B)	OIL'S TOTAL AMOUNT C=(AXB)	BIDDER'S RATE (D)	BIDDER'S AMOUNT E=(AXD)	PERCENTAGE Inc(+)/Dec(-)	SERVICE ACCOUNTING CODE (SAC)	SPECIFY % OF GST ON (C)
11	<u>Reinforced cement concrete work in column:</u> Reinforced cement concrete work in column beam walls (at any height thickness etc), including attached pilasters, as directed by Engineer-in charge.	270.00	M3	6,789	18,33,030.00					

12	Reinforcement for R.C.C. work: Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete	36,000	KG	64.28	2,314,080.00					
13	Brick masonry with common burnt clay: Brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in 1 Cement mortar 1:4 (1 cement : 4 coarse sand)	200.00	M3	6,680.55	13,36,110.00					
14	12mm cement plaster of mix:1:4 : Providing 12mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	1,800	M2	164.30	2,95,740.00					
15	Providing ,Supplying Structural steel: Providing ,Supplying Structural steel such as tees, angles channels and R.S. joists bolted welded fabricated as instructed by Engineer-in charge.	10,500.00	KG	64.22	6,74,310.00					
16	Wall painting with acrylic paint:	1,700	M2	80.23	1,36,391.00					

	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade to give an even shade									
17	<p>Providing and fixing concertina coil fence: Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre operable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre</p>	850	M	272.70	2,31,795.00					

